


Frames

منشآت تستخدم لتغطية بحور من أكثر من ٢٠م وتتميز بان لها عمق (depth) اقل وترخيم اقل (deflection) مقارنة بـ (Main girders)

Types of Frames

- 1-Three hinged Frame.
- 2-Two hinged frame.
- 3-Fixed Frame.
- 4-Cantilever Frame.
- 5-Continuous Frame.



- Three hinged Frame is usually used For spans (12 → 20m)
- It is better for weak soil [determinate structure].


Concrete Dimensions

$$t = \frac{L}{10}$$


$$b = \frac{30 \text{ cm}}{\frac{\text{spacing}}{20}}$$

ايهما اكبر

-Static System



نقوم بترحيل قواعد (Frame) للخارج مسافة (e) لضمان توزيع الاجهادات بانتظام على التربة (uniform stress)



Moment due to vertical reaction (y) = Moment due to hz Reaction(x)

$$y * e = x(t_{R.c.} + t_{p.c.})$$




$$e = \frac{x(t_{R.c.} + t_{p.c.})}{y}$$

-Steps of design

- 1-Get the loads on Secondary beams from load distribution and get their reactions on the frame.
- 2-Get the distributed loads on the frame.

$$w = \gamma_c b(t - t_s) * 1.40 + \frac{\Sigma Area}{span} w_s$$

- 3- Draw B.M.D , N.F.D. , S.F.D. of the Frame




4-Design section (1-1) , (2-2) and get Rft.

ملحوظة لاحظ ان الكمرات (B_1, B_2) فائدتها ما يلي

١ - الكمرة (B_1) تقلل (Buckling length) فى اتجاه (Out side Plan)


٢ - السلة (B_2) تتحمل الحائط و تقوم بتربيط ال (frames) ببعضها



spacing


spacing

Side view



KEY PLAN


1:200 → 1:400



(0.00)

$L(12-20m)$

Elevation




spacing



spacing

2-5m


Plan

R.F.T. of the Frame






Sec. (1-1)



Sec. (2-2)

Two Hinged Frame



– Two Hinged Frame is used for span (12 → 25)

–Concrete Dimensions


$$t = \frac{L}{12-14}$$

$$b = \left[\begin{array}{l} 30 \text{ cm} \\ \frac{\text{spacing}}{20} \end{array} \right] \quad \text{ايها اكبر}$$

–Statical System



نقوم بترحيل قواعد (Frame) للخارج مسافة (e) لضمان توزيع الاجهادات بانتظام على التربة (uniform stress)



Moment due to vertical reaction (y) = Moment due to hz
Reactin(x)

$$y * e = x(t_{R.c.} + t_{p.c.})$$



$$e = \frac{x(t_{R.c.} + t_{p.c.})}{y}$$

Steps of design




1-Get the loads on the secondary beams from load distribution and get their reactions on the frame.

2-Get the distributed load on the frame.


$$w_u = \gamma_c b(t - t_s) * 1.40 + \frac{\Sigma \text{Area}}{\text{span}} w_s$$

3-Solve the frame using virtual work Method
OR Moment Distribution Method.


4- Draw B.M.D , N.F.D. , S.F.D.




5-Design sections (1-1),(2-2),(3-3) and get rft.




Side view



Elevation




KEY PLAN


$$1:200 \rightarrow 1:400$$



Plan

$$+2-5m+$$

R.F.T. of the Frame









–Concrete Dimensions

$$t = \frac{L}{14-16} \quad b = \left[\begin{array}{l} 30 \text{ cm} \\ \frac{\text{spacing}}{20} \end{array} \right. \quad \text{ايها اكبر}$$

-Statical System



نقوم بترحيل قواعد (*Frame*) للخارج مسافة (*e*) لضمان توزيع الاجهادات بانتظام على التربة (*uniform stress*)



Moment due to vertical reaction (y) = Moment due to hz
 Reactin(x) + Moment due to (M)

$$y * e = x(t_{R.c.} + t_{p.c.}) + M$$



$$e = \frac{x(t_{R.c.} + t_{p.c.}) + M}{y}$$

Steps of design




1-Get the loads on the secondary beams from load distribution and get their reactions on the frame.

2-Get the distributed load on the frame.


$$w_u = \gamma_c b(t - t_s) * 1.40 + \frac{\Sigma \text{Area}}{\text{span}} w_s$$

3-Solve the frame using virtual work Method
 OR Moment Distribution Method.

4- Draw B.M.D , N.F.D. , S.F.D.




5-Design sections (1-1),(2-2),(3-3),(4-4) and get rft.



Side view

Elevation



KEY PLAN

$1:200 \rightarrow 1:400$


spacing

spacing

$2-5m$

Plan

R.F.T. of the Frame





Solved examples on frames

Example


For the given plan and cross-section, it is required to:

1- Draw structural plan and cross section to show all concrete elements.

2- Design the slabs and Main supporting given

$$f_{cu} = 27.5 \text{ N/mm}^2 \quad f_y = 360 \text{ N/mm}^2$$

$$F.C. = 1.5 \text{ kN/m}^2 \quad L.L. = 1.0 \text{ kN/m}^2$$



Solution

1-Design for solid slabs:

$$t_s = \frac{L_s}{24} = \frac{300}{24} = 12.50 \text{ cm}$$

take $t_s = 12 \text{ cm}$ for all slabs (check deflection)


$$w_{su} = 1.4(t_s \gamma_c + F.C.) + 1.6 L.L.$$

$$= 1.4[0.12 * 25 + 1.5] + 1.6 * 1.0$$

$$w_{su} = 7.90 \text{ kN/m}^2$$


Design of strip

Sec. (1-1)





$$100 = C_1 \sqrt{\frac{7.11 * 10^6}{1000 * 27.5}} \quad C_1 = 6.22, \quad J = 0.826$$

$$A_s = \frac{7.11 * 10^6}{0.826 * 100 * 360} = 239 \text{ mm}^2$$



KEY PLAN
1:200 → 1:400



Plan

Take $A_s = 5 \Phi 8/m'$ for all slabs

2- Design for secondary beams

For B_1


$$w_1 = \gamma_c b(t-t_s) * 1.4 + w_s \frac{L_s}{2}$$

$$w_1 = 25 * 0.25(0.5 - 0.12) * 1.40 + 7.9 * \frac{3.0}{2}$$

$$w_1 = 15.18 \text{ kN/m'}$$

$$R_1 = w_1 * \text{Spacing}$$

$$R_1 = 15.18 * 6 = 91.05 \text{ kN}$$



For B_2


$$w_2 = \gamma_c b(t-t_s) * 1.4 + w_s \cdot L_s$$

$$w_2 = 25 * 0.25(0.5 - 0.12) * 1.40 + 7.9 * 3.0$$

$$w_2 = 27.03 \text{ kN/m'}$$

$$R_2 = w_2 * \text{Spacing}$$

$$R_2 = 27.03 * 6 = 162.15 \text{ kN}$$



3-Design of Main System

$$\text{assume } b = 30 \text{ cm}, \quad t = \frac{L}{12-14} = \frac{18}{12-14} = 1.40 \text{ m}$$



$$w_{eq} = o.w + \frac{\sum P}{L}$$

$$w_{eq} = 25 * 0.3 * (1.4 - 0.12) * 1.40 + \frac{162.15 * 5 + 91.05 * 2}{18}$$

$$w_{eq} = 68.60 \text{ kN/m'}$$

$$h = 6.50 + 1.50 - 0.30 - 0.60 - \frac{1.40}{2} = 6.40 \text{ m}$$

By Eng. Ezz El-Din Mostafa & Eng. Yasser M. Samir



$$I_b = 349 * 10^{-4} * 1.02 * 1.4^3$$

$$I_b = 0.098 m^4$$

$$I_c = \frac{B(\frac{5}{6}t)^3}{12} = \frac{0.3 * (\frac{5}{6} * 1.40)^3}{12}$$


$$I_c = 0.0397 m^4$$

For Joint a

$$D.f_{ab} = \frac{0.75(I_c/h)}{(0.75 \frac{I_c}{h}) + (0.5 \frac{I_b}{L})}$$


$$D.f_{ab} = \frac{0.75 * (0.0397/6.40)}{0.75 * (0.0397/6.40) + 0.50 * (0.098/18)}$$

$$D.f_{ab} = 0.63$$






$$\frac{t_s}{t} = \frac{0.12}{1.40} = 0.086$$

$$\frac{b_0}{B} = \frac{0.3}{1.02} = 0.29$$



1166.89






Design of Sections

Sec. (1-1) $M_{u.l.} = 1166.89 \text{ kN.m}$ $N_{u.l.} = 617.64 \text{ kN.m}$

$b = 300 \text{ mm}$, $t = 1400 \text{ mm}$



$$\frac{N_{u.l.}}{b t f_{cu}} = \frac{617.64 \cdot 10^3}{300 \cdot 1400 \cdot 27.5} = 0.05 > 0.04 \quad (\text{Don't neglect } N_{u.l.})$$

$$e = \frac{M_{u.l.}}{N_{u.l.}} = \frac{1166.89}{617.64} = 1.89 \text{ m}$$

$$\frac{e}{t} = \frac{1.89}{1.40} = 1.35 > 0.5 \quad (\text{big eccentricity})$$

$$e_s = e + \frac{t}{2} - c = 1.89 + \frac{1.40}{2} - 0.1 = 2.49 \text{ m}$$

$$M_{us} = 617.64 \cdot 2.49 = 1537.9 \text{ kN.m}$$

$$d = C_1 \sqrt{\frac{M_{us}}{b \cdot f_{cu}}}$$

$$1300 = C_1 \sqrt{\frac{1537.9 \cdot 10^6}{300 \cdot 27.5}} \quad C_1 = 3.01 \quad \& \quad J = 0.752$$

$$A_s = \frac{M_{us}}{J \cdot d \cdot f_y} - \frac{N_{us}}{f_y / \gamma_s}$$

$$A_s = \frac{1537.9 \cdot 10^6}{0.752 \cdot 1300 \cdot 360} - \frac{617.64 \cdot 10^3}{360 / 1.15}$$

$$A_s = 24 \text{ cm}^2 = 7 \phi 22$$

$$N_{u.l.} = 209.81 \text{ kN.m}$$

$t = 1400 \text{ mm}$


$$\frac{N_{u.l.}}{b t f_{cu}} = \frac{209.81 * 10^3}{300 * 1400 * 27.5} = 0.018 < 0.04 \quad (\text{neglect } N_{u.l.})$$

$$d=C_1 \sqrt{\frac{Mu.l.}{b*f_{cu}}}$$

$$1300 = C_1 \sqrt{\frac{1166.89 * 10^6}{300 * 27.5}} \quad C_1 = 3.46 \quad \& \quad J = 0.778$$

$$A_s = \frac{1166.89 \cdot 10^6}{0.778 \cdot 1300 \cdot 360}$$

$$A_s = 32.05 \text{ cm}^2 = 9\#22$$



$$N_{u.l.} = 209.81 \text{ kN.m}$$

$t = 1400 \text{ mm}$

$$\frac{N_{u.l.}}{b t f_{cu}} = \frac{209.81 * 10^3}{300 * 1400 * 27.5} = 0.018 < 0.04 \quad (\text{neglect } N_{u.l.})$$

$$B = \begin{cases} 16ts + b = 16 \cdot 120 + 300 = 2220 \text{ mm} \\ \mathcal{L} \longrightarrow \mathcal{L} = 6000 \text{ mm} \\ \frac{KL}{5} + b = \frac{0.76 \cdot 18000}{5} + 300 = 3036 \text{ mm} \end{cases}$$


$$B=2220mm$$

$$d=C_1 \sqrt{\frac{Mu.l.}{B*f_{cu}}}$$

$$1300 = C_1 \sqrt{\frac{1611.4 * 10^6}{2220 * 27.5}} \quad C_1 = 8.0 \quad \& \quad J = 0.826$$

$$A_s = \frac{1611.4 * 10^6}{0.826 * 1300 * 360}$$

$$A_s = 41.68 \text{ cm}^2 = 9\#25$$



Check Shear

$$Q_{cr} = Q_{max} - w \left(\frac{c}{2} + \frac{d}{2} \right)$$

$$Q_{cr} = 526.59 - 58.51 \left(\frac{1.40}{2} + \frac{1.30}{2} \right)$$

$$Q_{cr} = 447.60 \text{ kN}$$

$$q_{su} = \frac{Q_{cr}}{bd} = \frac{447.60 \cdot 10^3}{300 \cdot 1300} = 1.15 \text{ N/mm}^2$$

$$q_{cu} = 0.24 \sqrt{\frac{27.5}{1.5}} = 1.03 \text{ N/mm}^2$$

$$q_{cu} < q_u < q_{u\max}$$

$$q_{\max} = 0.7 \sqrt{\frac{27.5}{1.5}} = 3.00 \text{ N/mm}^2$$


$$q_u - \frac{q_{cu}}{2} = \frac{n A_s f_y}{b S} \gamma_s$$


$$\text{assume } n=2 \quad A_s = 78.5 \text{ mm}^2 = \phi 10$$

$$1.15 - \frac{1.03}{2} = \frac{2 \cdot 78.5 \cdot 240 / 1.15}{300 \cdot S} \quad \longrightarrow \quad S = 172 \text{ mm}$$

$$\text{No. of stirrups/m} = \frac{1000}{S} = 5.8 \quad \text{Take Stirrups } 6\phi 10/\text{m}$$

R.F.T. of the Frame





Example

For the given plan and cross-section, Columns are only allowed on the outside perimeter

it is required to:

- 1- Draw structural plan and Elevation to show all concrete elements.
- 2- Design the slabs and Main supporting element.


Use Blocks(200*200*400)

O.W.(blocks)=0.15 kN/block

given

$$f_{cu}=30\text{N/mm}^2 \quad f_y=360\text{N/mm}^2 \quad F.C.=1.5\text{kN/m}^2$$

$$L.L.=2.0\text{kN/m}^2$$



Solution



For one way H.B. Slabs.

assume $t = 250\text{mm}$ & $t_s = 50\text{mm}$ & $h = 200\text{mm}$

$$w_{u.l} = 1.4(t_s \gamma_c + f.c. + 2bh\gamma_c + 10 * \text{wt. of Block}) + 1.6 L.L$$

$$w_{u.l} = 1.4(0.05 * 25 + 1.5 + 2 * 0.1 * 0.2 * 25 + 10 * 0.15) + 1.6 * 2.0$$

$$w_{u.l} = 10.55 \text{ kN/m} \quad w_{rib} = 5.27 \text{ kN/m}$$



Design of Sections.

Sec. (1-1) $M_{u.l.} = 18.97 \text{ kN.m}$
 $d = 250 - 30 = 220 \text{ mm}$

$$d = C_1 \sqrt{\frac{M_{u.l.}}{f_{cu} * b}} \quad 220 = C_1 \sqrt{\frac{18.97 * 10^6}{30 * 500}} \quad \begin{matrix} C_1 = 6.2 \\ J = 0.826 \end{matrix}$$

$$A_s = \frac{M_{u.l.}}{J f_y d} = \frac{18.97 * 10^6}{360 * 0.826 * 220} = 290 \text{ mm}^2/\text{rib}$$

$1\phi 12 + 1\phi 16/\text{rib}$

Sec. (2-2) $M_{u.l.} = 15.81 \text{ kN.m}$

$$d = C_1 \sqrt{\frac{M_{u.l.}}{f_{cu} * b}} \quad 220 = C_1 \sqrt{\frac{15.81 * 10^6}{30 * 500}} \quad \begin{matrix} C_1 = 6.8 \\ J = 0.826 \end{matrix}$$

$$A_s = \frac{M_{u.l.}}{J f_y d} = \frac{15.81 * 10^6}{360 * 0.826 * 220} = 242 \text{ mm}^2/\text{rib}$$

$1\phi 12 + 1\phi 16/\text{rib}$

Sec. (3-3) $M_{u.l.} = 7.9 \text{ kN.m}$


$$d = C_1 \sqrt{\frac{M_{u.l.}}{f_{cu} * b}} \quad 220 = C_1 \sqrt{\frac{7.9 * 10^6}{30 * 500}} \quad \begin{matrix} C_1 = 9.5 \\ J = 0.826 \end{matrix}$$

$$A_s = \frac{M_{u.l.}}{J f_y d} = \frac{7.9 * 10^6}{360 * 0.826 * 220} = 121 \text{ mm}^2/\text{rib}$$


$2\phi 10/\text{rib}$

كمره للتربيط


option



Elevation



KEY PLAN





Design of Main System

Assume $b=35\text{cm}$, $t=\frac{L}{14-16} = 1.5\text{m}$

$$w = o.w + w_s * S$$

$$o.w. = 25 * 0.35 (1.5 - 0.25) * 1.40 = 15.3 \text{ kN/m'}$$

$$w = 10.55 * 6 + 15.3 = 78.6 \text{ kN/m}$$



Relative Stiffness, D.F.

$$\frac{I_b}{t} = \frac{0.25}{1.5} = 0.17 \quad \text{Old tables page 91} \quad \mu = 600$$

$$\frac{b}{B} = \frac{0.35}{0.6} = 0.58$$

$$I_b = 600 * 10^{-4} * 0.6 * 1.5^3 = 0.121 \text{ m}^4$$

$$\frac{I_c}{12} = \frac{bt^3}{12} = \frac{0.35 * 1.5^3}{12} = 0.098 \text{ m}^4$$

$$K_{ab} = \frac{I_c}{h} = \frac{0.098}{6.35} = 0.015$$

لاحظ ان هذا الارتفاع يقاس من
وجه القواعد الى C.L. ال girder


$$K_{aa} = \frac{1}{2} \frac{I_b}{L} = \frac{1}{2} * \frac{0.121}{20.0} = 0.003$$

$$D.F_{ab} = \frac{K_{ab}}{K_{ab} + K_{aa}} = \frac{0.015}{0.015 + 0.003} = 0.833$$

Fixed End Moment



$$M = \frac{wL^2}{12} = \frac{78.6 * 20^2}{12} = 2620 \text{ kN.m}$$

B.M.D.



$$\therefore X = 517.2 \text{ kN}$$

$$\therefore Y = \frac{\Sigma \text{Loads}}{2} = \frac{78.6 * 20}{2} = 786 \text{ kN}$$



Sec(1-1): R-Sec $M_{u.l.} = 2182.5 \text{ kN.m}$, $d = 1400$, $b = 350 \text{ mm}$

$$N_{u.l.} = 517.2 \text{ kN}$$

$$\frac{N_{u.l.}}{f_{cu} * bt} = \frac{517.2 * 10^3}{30 * 350 * 1400} = 0.035 > 0.04 \quad (\text{neglect N.F.})$$

$$d = C_1 \sqrt{\frac{M_{u.l.}}{b * f_{cu}}}$$

$$1400 = C_1 \sqrt{\frac{2182.5 * 10^6}{350 * 30}} \quad C_1 = 3.07 \quad J = 0.75$$

$$A_s = \frac{2182.5 * 10^6}{0.75 * 1400 * 360}$$

$$A_s = 5773 \text{ mm}^2$$

12Ø25

Sec(2-2): R-Sec $M_{u.l.} = 2182.5 \text{ kN.m}$, $d = 1400$, $b = 350 \text{ mm}$

$$N_{u.l.} = 786 \text{ kN}$$

$$\frac{N_{u.l.}}{f_{cu} * bt} = \frac{786 * 10^3}{30 * 350 * 1400} = 0.053 > 0.04 \quad (\text{use N.F.})$$

$$e = \frac{M_{u.l.}}{N_{u.l.}} = \frac{2182.5}{786} = 2.78 \text{ m} \quad \frac{e}{t} = \frac{2.78}{1.5} = 1.85 > 0.5$$

⇒ Big ecc.

$$e_s = e + \frac{t}{2} - c = 2.78 + \frac{1.5}{2} - 0.1 = 3.43 \text{ m}$$

$$M_{us} = N_{u.l.} * e_s = 786 * 3.43 = 2696 \text{ kN.m}$$

$$d = C_1 \sqrt{\frac{M_{us}}{f_{cu} b}} \quad 1400 = C_1 \sqrt{\frac{2696 * 10^6}{30 * 350}} \quad C_1 = 2.78$$
$$J = 0.71$$

$$A_s = \frac{M_{us}}{f_y J d} - \frac{N_{u.l.}}{f_y/\gamma_s}$$

$$A_s = \frac{2696*10^6}{360*0.71*1400} - \frac{786*10^3}{360/1.15} = 5023 \text{ mm}^2$$

check A_{smin}

11Ø25

$$A_{smin} = \frac{1.1}{f_y} b d = 1711 \text{ mm}^2$$

Sec(3-3): T-Sec $M_{u.l.} = 1747.5 \text{ kN.m}$, $d = 1400$

$$N_{u.l.} = 517.2 \text{ kN} \quad B = 600 \text{ mm}$$

Neglect $N_{u.l.}$

$$1400 = C_1 \sqrt{\frac{1747.5*10^6}{600*30}} \implies C_1 = 4.49 \quad J = 0.82$$

$$A_s = \frac{1747.5*10^6}{0.82*1400*360} = 4228 \text{ mm}^2 \quad \textbf{9Ø25}$$

Sec(4-4): R-Sec $M_{u.l.} = 1091.3 \text{ kN.m}$, $d = 1400$, $b = 350 \text{ mm}$

$$N_{u.l.} = 786 \text{ kN}$$

$$\frac{N_{u.l.}}{F_{cu} * b t} = \frac{786*10^3}{30*350*1400} = 0.053 > 0.04 \quad (\text{ use N.F. })$$

$$e = \frac{M_{u.l.}}{N_{u.l.}} = \frac{1091.3}{786} = 1.39 \text{ m} \quad \frac{e}{t} = \frac{1.39}{1.5} = 0.93$$

\implies **Big ecc.**

$$e_s = e + \frac{t}{2} - c = 1.39 + \frac{1.5}{2} - 0.1 = 2.04 \text{ m}$$

$$M_{us} = N_{u.l.} * e_s = 786 * 2.04 = 1603 \text{ kN.m}$$

$$d = C_1 \sqrt{\frac{M_{us}}{f_{cu} b}} \quad 1400 = C_1 \sqrt{\frac{1603*10^6}{30*350}} \quad C_1 = 3.58$$

$$J = 0.78$$

$$A_s = \frac{M_{us}}{f_y J d} - \frac{N_{u.l.}}{f_y / \gamma_s}$$

$$A_s = \frac{1603 \cdot 10^6}{360 \cdot 0.78 \cdot 1400} - \frac{786 \cdot 10^3}{360 / 1.15} = 1566 \text{ mm}^2$$

check A_{smin}

5Ø22

$$A_{smin} = \frac{1.1}{f_y} b d = 1497 \text{ mm}^2 \text{ O.K.}$$

Check Shear

$$Q_{cr} = Q_{max} - w \left(\frac{c}{2} + \frac{d}{2} \right)$$

$$Q_{cr} = 786 - 78.6 \left(\frac{1.40}{2} + \frac{1.30}{2} \right)$$

$$Q_{cr} = 679.9 \text{ kN}$$

$$q_{su} = \frac{Q_{cr}}{b d} = \frac{679.9 \cdot 10^3}{350 \cdot 1400} = 1.39 \text{ N/mm}^2$$

$$q_{cu} = 0.24 \sqrt{\frac{30}{1.5}} = 1.07 \text{ N/mm}^2$$

$$q_{cu} < q_u < q_{u_{max}}$$

$$q_{max} = 0.7 \sqrt{\frac{30}{1.5}} = 3.13 \text{ N/mm}^2$$

$$q_u - \frac{q_{cu}}{2} = \frac{n A_s f_y}{b S} / \gamma_s$$



assume $n=2$


$$A_s = 78.5 \text{ mm}^2 = \phi 10$$

$$1.39 - \frac{1.07}{2} = \frac{2 \cdot 78.5 \cdot 240 / 1.15}{350 \cdot S} \longrightarrow S = 109 \text{ mm}$$


$$\text{No. of stirrups/m} = \frac{1000}{S} = 9.1 \quad \text{Take Stirrups } 10\phi 10/\text{m}$$

R.F.T. of the Frame







Sec.(3-3)



Sec.(2-2)



Sec.(1-1)



Sec.(4-4)

Example



For the given plan and cross-section, it is required to:

- 1- Draw structural plan and cross section to show all concrete elements.
- 2- Design the main supporting elements.

given Use all Sec. Beams 25*50

$$f_{cu} = 25 \text{ N/mm}^2 \quad f_y = 360 \text{ N/mm}^2$$

$$F.C. = 1.5 \text{ kN/m}^2 \quad L.L. = 1.0 \text{ kN/m}^2$$



Sec.(1-1)

clear height = 5.5m

Solution

$$t_s = \frac{400}{40} = 10 \text{ cm} \quad \text{For sky light} \quad t_s = \frac{400}{35} = 11.43 \text{ cm}$$

Take $t_s = 10 \text{ cm}$ For all slabs except sky light,

take $t_s = 12 \text{ cm}$

$$\text{For } t_s = 12 \text{ cm} \quad w_{su} = 1.4[t_s \gamma_c + F.c.] + 1.6 \text{ L.L.}$$


$$w_{su} = 1.4[0.12 * 25 + 1.5] + 1.6 * 1 = 7.91 \text{ kN/m}^2$$


$$\text{For } t_s = 10 \text{ cm} \quad w_{su} = 1.4[0.10 * 25 + 1.5] + 1.6 * 1 = 7.2 \text{ kN/m}^2$$


1-Analysis of Beams

For B_1

$$C_a = 1 - \frac{1}{2} * \frac{4}{5} = 0.60$$








Plan

level (9.00)



Plan


level (7.00)

$$w_a = \gamma_c b(t - t_s) * 1.40 + C_a \frac{L_s}{2} w_s$$


$$= 25 * 0.25 [0.5 - 0.10] * 1.40 + 0.6 * \frac{4}{2} * 7.20$$

$$w_a = 12.14 \text{ kN/m'}$$

$$R_1 = 12.14 * 5 = 60.7 \text{ kN}$$



For B₂




$$w_a = \gamma_c b(t - t_s) * 1.40 + C_a \frac{L_s}{2} w_s * 2$$

$$= 25 * 0.25 [0.5 - 0.10] * 1.40 + 0.6 * \frac{4}{2} * 7.20 * 2$$

$$w_a = 20.78 \text{ kN/m'}$$

$$R_2 = 20.78 * 5 = 103.9 \text{ kN}$$



For sky light

For B₃

$$w_a = 25 * 0.25 [0.5 - 0.12] * 1.40 + 0.6 * \frac{4}{2} * 7.90$$

$$w_a = 12.81 \text{ kN/m'}$$


$$R_3 = 12.81 * 5 = 64.03 \text{ kN}$$

For B₄

$$w_a = 25 * 0.25 [0.5 - 0.12] * 1.40 + 0.6 * \frac{4}{2} * 7.9 * 2$$

$$w_a = 19.13 \text{ kN/m'}$$

$$R_4 = 19.13 * 2 = 38.25 \text{ kN}$$



For Frame(1)

$$b = 30 \text{ cm}$$

$$t = \frac{20}{12-14} = 1.5 \text{ m}$$

$$P_1 = 60.70 \text{ kN} , \quad P_2 = 103.9 \text{ kN}$$

$$P_3 = R_1 + R_3 + R_4 + o.w \text{ of Post}$$


$$= 60.7 + 64.03 + 38.25 + 0.25 * 0.25 * 25 * 1.4 * 2$$

$$P_3 = 167.36 \text{ kN}$$

$$w_a = w_e = \gamma_c b (t - t_s) * 1.40 + \frac{\Sigma A}{S_{pan}} w_s$$

$$= 25 * 0.3 [1.5 - 0.1] * 1.40 + \frac{4 * 2 * 0.5 * 8}{2.0} * 7.2$$



$$w_a = w_e = 26.22 \text{ kN/m'}$$



$$I_c = \frac{0.3 * (\frac{5}{6} * 1.5)^3}{12} = 0.049 \text{ m}^4$$

To get I_b :

we have two cross-sections



at midspan



$$I_{b2} = 363 * 10^{-4} * 0.9 * 1.5^3$$

$$I_{b2} = 0.11 \text{ m}^4$$

$$I_{b1} = 0.3 * \frac{1.5^3}{12} = 0.084 \text{ m}^4$$

$$I_{av.} = \frac{0.11 * 16 + 0.084 * 4}{20} = 0.10 \text{ m}^4$$

$$D.f_{ab} = \frac{0.75 * (0.049/7)}{0.75(\frac{0.049}{7}) + 0.5(\frac{0.11}{20})} = 0.68$$



Sec(1-1)

$$\frac{N_u}{bt f_{cu}} = \frac{594.16 \cdot 10^3}{300 \cdot 1500 \cdot 25} = 0.053 > 0.04 \text{ (Don't neglect } N)$$

$$e = \frac{M}{N} = \frac{1366.67}{594.16} = 2.3m$$

$$\frac{e}{t} = \frac{2.3}{1.5} = 1.5 > 0.5 \text{ (big eccentricity)}$$

$$e_s = e + \frac{t}{2} - c = 2.3 + \frac{1.5}{2} - 0.1 = 2.95m$$

$$M_{us} = N \cdot e_s = 594.16 \cdot 2.95 = 1752.87 kN.m$$

$$1400 = C_1 \sqrt{\frac{1752.87 \cdot 10^6}{300 \cdot 25}} \quad C_1 = 2.90 \quad J = 0.73$$

$$A_s = \frac{1752.87 \cdot 10^6}{0.73 \cdot 1400 \cdot 360} - \frac{594.16 \cdot 10^3}{(360/1.15)} = 28.58 cm^2$$

8Ø22

Sec. (2-2)

$$\frac{N}{bt f_{cu}} = \frac{195.24 \cdot 10^3}{300 \cdot 1500 \cdot 25} = 0.017 < 0.04 \text{ (neglect } N)$$

$$1400 = C_1 \sqrt{\frac{1366.67 \cdot 10^6}{300 \cdot 25}} \quad C_1 = 3.28 \quad J = 0.77$$

$$A_s = \frac{1366.67 \cdot 10^6}{0.77 \cdot 1400 \cdot 360} = 35.37 cm^2$$


10Ø22

Sec. (3-3)

$$R\text{-Sec} \quad b = 300mm, \quad d = 1400mm$$

$$, \quad M_{ul} = 1698.81 kN.m, \quad N_{u.l} \text{ (neglected)}$$

لاحظ أن Sec(3-3) هو R-Sec صريح



$$1400 = C_1 \sqrt{\frac{1698.81 \cdot 10^6}{300 \cdot 25}} \quad C_1 = 2.94 \quad J = 0.74$$

$$A_s = \frac{1698.81 \cdot 10^6}{0.74 \cdot 1400 \cdot 360} = 45.76 \text{ cm}^2$$

10Ø25

Check Shear

$$Q_{cr} = Q_{max} - w \left(\frac{c}{2} + \frac{d}{2} \right)$$

$$Q_{cr} = 533 - 26.2 \left(\frac{1.50}{2} + \frac{1.40}{2} \right)$$

$$Q_{cr} = 495 \text{ kN}$$

$$q_{su} = \frac{Q_{cr}}{bd} = \frac{495 \cdot 10^3}{300 \cdot 1400} = 1.18 \text{ N/mm}^2$$

$$q_{cu} = 0.24 \sqrt{\frac{25}{1.5}} = 0.98 \text{ N/mm}^2$$

$$q_{cu} < q_u < q_{u_{max}}$$

$$q_{max} = 0.7 \sqrt{\frac{25}{1.5}} = 2.86 \text{ N/mm}^2$$


$$q_u - \frac{q_{cu}}{2} = \frac{n A_s f_y}{b S}$$


$$\text{assume } n=2 \quad A_s = 78.5 \text{ mm}^2 = \phi 10$$

$$1.18 - \frac{0.98}{2} = \frac{2 \cdot 78.5 \cdot 240 / 1.15}{300 \cdot S} \quad \longrightarrow \quad S = 158 \text{ mm}$$

$$\text{No. of stirrups/m} = \frac{1000}{S} = 6.3 \quad \text{Take Stirrups } 7\phi 10/\text{m}$$

R.F.T. of the Frame





Example



For the given plan and cross-section, it is required to:

- 1- Draw structural plan and cross section to show all concrete elements.
- 2- Design the slabs and Main supporting element.


given Use Sec. Beams 25*50



$$f_{cu} = 25 \text{ N/mm}^2 \quad f_y = 360 \text{ N/mm}^2$$

$$F.C. = 1.5 \text{ kN/m}^2 \quad L.L. = 1.0 \text{ kN/m}^2$$




Solution





KEY PLAN

1:200 → 1:400



1- Design of slabs


$$t_s = \frac{500}{45} = 11.11 \text{ cm}$$

Take $t_s = 12 \text{ cm}$ For all slabs

$$w_{su} = 1.4[t_s \gamma_c + F.c.] + 1.6 \text{ L.L.} \cos \theta$$

$$w_{su} = 1.4[0.12 * 25 + 1.5] + 1.6 * 1.0 * 0.98$$

$$w_{su} = 7.87 \text{ kN/m}^2$$



$$\theta = \tan^{-1}\left(\frac{2}{10}\right)$$

$$\theta = 11.31$$

$$\cos \theta = 0.98$$


Strip(1)

Sec. (1-1) $d = 120 - 30 = 90 \text{ mm}$


$$90 = C_1 \sqrt{\frac{6.83 * 10^6}{1000 * 25}} \quad C_1 = 5.44 \quad J = 0.826$$

$$A_s = \frac{6.83 * 10^6}{0.826 * 360 * 90} = 255 \text{ mm}^2 / \text{m}'$$

$$A_s = 5 \Phi 8 / \text{m}'$$



Strip(2)



Sec. (1-1) $d = 120 - 20 = 100 \text{ mm}$


$$100 = C_1 \sqrt{\frac{7.08 * 10^6}{1000 * 25}} \quad C_1 = 5.3 \quad J = 0.826$$

$$A_s = \frac{7.08 * 10^6}{0.826 * 360 * 100} = 238 \text{ mm}^2 / \text{m}'$$

$$A_s = 5 \Phi 8 / \text{m}'$$

2-Analysis of Beams

For B_1




Assume beams(25*50)


$$w_a = \gamma_c b(t - t_s) * 1.40 + C_a \frac{L_s}{2} w_s$$

$$= 25 * 0.25 [0.5 - 0.12] * 1.40 + 0.5 * \frac{5}{2} * 7.87$$

$$w_a = 13.16 \text{ kN/m'}$$




For B_2




$$w_a = \gamma_c b(t - t_s) * 1.40 + C_a \frac{L_s}{2} w_s * 2$$

$$= 25 * 0.25 [0.5 - 0.12] * 1.40 + 0.5 * \frac{5}{2} * 7.87 * 2$$

$$w_a = 23 \text{ kN/m'}$$



3-Analysis of Main system




assume $b=30\text{cm}$, $t = \frac{L}{12-14} = \frac{20}{12-14} = 1.6\text{m}$

Load For Shear = Load for Moment



$$w_a = w_e = \gamma_c b(t-t_s) * 1.40 + \frac{\Sigma A}{\text{Span}} w_s$$

$$= 25 * 0.3 [1.6 - 0.12] * 1.40 + \frac{6.50 * 8}{20.4} * 7.87$$

$$w_a = w_e = 35.6 \text{ kN/m'}$$



we have to use virtual work method in this example, because if we use moment distribution , we have to make sway correction.




$$\delta_{10} = \frac{M_0 M_1}{EI}$$

$$\delta_{11} = \frac{M_1^2}{EI}$$

$$I_c = \frac{0.3 * (\frac{5}{6} * 1.6)^3}{12} = 0.059 m^4$$

$$I_b = \mu B t^3 * 10^{-4}$$

$$= 341 * 1.02 * 1.6^3 * 10^{-4} = 0.143 m^4$$



$$\frac{t_s}{t} = \frac{0.12}{1.60} = 0.075$$

$$\frac{b_0}{B} = \frac{0.3}{1.02} = 0.29$$

$$\delta_{10} = -\frac{1}{3} * \frac{5.10}{E_c I_b} [2224.2 * 7 + 2224.2 * \frac{6}{2}] * 2$$

$$- \frac{1}{3} * \frac{5.10}{E_c I_b} [2224.2 * 7 + 2965.6 * 8 + \frac{2224.2 * 8}{2} + \frac{2965.6 * 7}{2}] * 2$$

$$- \frac{2}{3} * \frac{5.10}{E_c I_b} [\frac{35.6 * 5.1 * 5}{8} * 6.50] * 2 - \frac{2}{3} * \frac{5.10}{E_c I_b} [\frac{35.6 * 5.1 * 5}{8} * 7.5] * 2$$

$$\delta_{10} = \frac{-1996962.567}{E_c}$$



$$\delta_{11} = \frac{1}{3} * \frac{6}{E_c I_b} [6 * 6] * 2 + \frac{1}{3} * \frac{10.2}{E_c I_b} [6^2 + 8^2 + 6 * 8] * 2$$

$$\delta_{11} = \frac{9478.44}{E_c}$$

$$\delta_{10} + x \delta_{11} = 0$$

$$-\frac{1996962.567}{E_c} + \frac{9478.44}{E_c} X = 0$$

$$X = 210.68 \text{ kN}$$



Sec(1-1)

$$\frac{N_{u.l.}}{b \ t \ f_{cu}} = \frac{601.43*10^3}{300*1600*25} = 0.05 > 0.04 (\text{Don't neglect})$$

$$e = \frac{M_{u.l.}}{N_{u.l.}} = \frac{1264.11}{601.43} = 2.10m$$

$$\frac{e}{t} = \frac{2.1}{1.6} = 1.3 > 0.5 (\text{big eccentricity})$$

$$e_s = e + \frac{t}{2} - c = 2.1 + \frac{1.6}{2} - 0.1 = 2.80m$$

$$M_{us} = N_{u.l.} * e_s = 601.43 * 2.80 = 1685.11 kN.m$$

$$1500 = C_1 \sqrt{\frac{1685.11*10^6}{300*25}} \quad C_1 = 3.16 \quad J = 0.76$$

$$A_s = \frac{1685.11*10^6}{0.76*1500*360} - \frac{601.43*10^3}{360/1.15} = 21.96 cm^2$$

6Ø22

Sec. (2-2)

$$\frac{N_{u.l.}}{b \ t \ f_{cu}} = \frac{311.63*10^3}{300*1600*25} = 0.02 < 0.04 (\text{neglect } N)$$

$$1500 = C_1 \sqrt{\frac{1264.11*10^6}{300*25}} \quad C_1 = 3.65 \quad J = 0.79$$

$$A_s = \frac{1264.11*10^6}{0.79*1500*360} = 29.67 cm^2$$

8Ø22

Sec(3-3)

$$N_{u.l.} = 217.87 \text{ kN} \quad (\text{neglect } N)$$

$$M_{u.l.} = 1280.12 \text{ kN.m}$$

$$B = \begin{cases} 16*120 + 300 = 2220 \\ 5000 \\ \frac{0.76*20.4*1000}{5} + 300 = 3400 \end{cases}$$

$$B = 2220 \text{ mm}$$

$$1500 = C_1 \sqrt{\frac{1220.12*10^6}{2220*25}} \quad C_1 = 9.88 \quad J = 0.826$$

$$A_s = \frac{1280.12*10^6}{0.826*1500*360} = 28.70 \text{ cm}^2$$

8Ø22

Check Shear

$$Q_{cr} = Q_{max} - w \left[\frac{C}{2} + \frac{d}{2} \right] \cos \theta$$

$$Q_{cr} = 483.93 - 35.6 \left[\frac{1.60}{2} + \frac{1.50}{2} \right] \cos \theta$$


$$Q_w = 429.79 \text{ kN}$$

$$q_{su} = \frac{Q_{cr}}{bd} = \frac{429.79*10^3}{300*1500} = 0.96 \text{ N/mm}^2$$


$$q_{cu} = 0.24 \sqrt{\frac{25}{1.5}} = 0.98 \text{ N/mm}^2$$

$$q_{su} < q_{cu} \quad 5\phi 8 / m'$$

R.F.T. of the Frame



R.F.T. of the Frame





By Eng. Ezz El-Din Mostafa & Eng. Yasser M. Samir

Example

For the given plan and cross-section, it is required to:

- 1- Draw structural plan and cross section to show all concrete elements.
- 2- Show how to solve the main system




Solution

1-Design for solid slabs:


$$t_s = \frac{L_s}{20} = \frac{500}{35} = 14.2 \text{ cm}$$


take $t_s = 15 \text{ cm}$ for all slabs (check deflection)

Strip(1)




Strip(2)






حاول تخيل شكل البلاطات



Elevation




Plan

2- Design for secondary beams

For B_1

$$w_1 = \gamma_c b(t - t_s) * 1.4 + w_s \frac{L_s}{2}$$





$$R_1 = w_1 * \text{Spacing}$$



3-Design of Main System

assume $b = 30\text{cm}$, $t = \frac{L}{12-14} = \frac{18}{12-14} = 1.40\text{m}$



$$w_{eq} = 0.7w + \frac{\sum P}{L}$$




Example

For the given plan and cross-section, it is required to:



Draw structural plan and cross section to show all concrete elements.



Sec. (1-1)




حاول تخیل شکل البعطات




Example


For the given plan and cross-section,
it is required to:

Draw structural plan and cross
section to show all concrete elements.






حاول تفخيل شكل البلاطات





Plan




Example


For the given plan and cross-section,
it is required to:

Draw structural plan and cross
section to show all concrete elements.







حاول تتخيل شكل البلاطات



لا حظ ان هذا الحل لا يفتح في حالة وجود شبائك




Saw Tooth Supported on a system

إذا كانت المسافة بين الأعمدة أكبر من ١٢ م فإننا نختار أحد الأنظمة الإنشائية مثل وذلك حسب الطول القصير للأرض واتجاه (Saw tooth)

Example

For the given plan, it is required to:

- 1-Choose the suitable system to cover this Area.
- 2-Design all Slabs and draw plan of Rft.
- 3-Design the main supporting element and draw details of Rft.



$$F.C. = 1.5 \text{ kN/m}^2, L.L. = 0.5 \text{ kN/m}^2$$


$$f_{cu} = 25 \text{ N/mm}^2, f_y = 360 \text{ N/mm}^2$$

Columns are only allowed on perimeter

Solution

$$t = \frac{671}{16} = 41.94 \text{ cm}$$

$$\text{take } t = 25 \text{ cm } [20 \text{ cm} + 5 \text{ cm}]$$




$$\theta = \tan^{-1}\left(\frac{3}{6.0}\right) = 26.57$$

$$w_{su} = 1.4(t_s \gamma_c + F.C. + 2bh \gamma_c + 10 * \text{wt. of block}) + 1.6 L.L. \cos \theta$$

$$w_{su} = 1.4(0.05 * 25 + 1.5 + 2 * 0.1 * 0.2 * 25 + 10 * 0.15) + 1.6 * 0.5 * 0.89$$






$$w_{su} = 8.06 \text{ kN/m}^2$$

$$w_{su/\text{Rib}} = 0.5 * 8.06 = 4.03 \text{ kN/m}$$





حاول تخيل شكل البعاطات

لا حظ في هذه الحالة يكون (Frame) يحل محل (Y-beam)



KEY PLAN
1:200 → 1:400



Sec. (1-1)

$$220 = C_1 \sqrt{\frac{20.28 \cdot 10^6}{500 \cdot 25}} \quad C_1 = 5.46 \quad J = 0.826$$

$$A_s = \frac{20.28 \cdot 10^6}{0.826 \cdot 360 \cdot 220} = 3.10 \text{ cm}^2 / \text{rib}$$

$$A_s = 2 \Phi 16 / \text{rib}$$


Sec. (2-2)

$$A_s = 2 \Phi 10 / \text{rib}$$

2] Reactions of slabs on beams

$$R = y = w_{su} \cdot \frac{L}{2} \quad \text{kN/m}$$

$$R = y = 8.06 \cdot 6.71 / 2 = 27.04 \text{ kN/m}$$




3] Analysis of Ridge beam (250*400)

$$w = R + o.w \quad \text{kN/m}$$

$$w = 27.04 + 0.25 \cdot 0.40 \cdot 25 \cdot 1.40$$

$$w = 30.54 \text{ kN/m}$$



$$R_1 = 30.54 \cdot 2.5 = 76.35 \text{ kN}$$


4] Design of Posts

$$R_p = R_1 + o.w \text{ of Post}$$

$$R_p = 76.35 + 0.25 * 0.25 * 3 * 25 * 1.40 = 82.91 \text{ kN}$$

$$82.91 * 10^3 = 0.35 * 250 * 250 * 25 + 0.67 A_s f_y$$

$$A_s = -ve \rightarrow A_s = 4\phi 13$$







5] Design of main system

لاحظ في هذه الحالة يكون (Frame) هو نفسه (Y-beam)


$$w_f = o.w. + y + \frac{\Sigma R_p}{Span} \text{ kN/m}$$

$$w_f = 0.30 * 1.50 * 25 * 1.40 + 27.04 + \frac{8 * 82.91}{20.0}$$

$$w_f = 75.95 \text{ kN/m}$$



$$I_b = 0.3 * \frac{1.5^3}{12} = 0.084 \text{ m}^4$$



$$I_c = \frac{0.30 * \left(\frac{5}{6} * 1.50 \right)^3}{12}$$

$$I_c = 0.049 \text{ m}^4$$


For Joint a

$$D.f_{ab} = \frac{0.75(I_c/h)}{(0.75 \frac{I_c}{h}) + (0.5 \frac{I_b}{L})}$$

$$D.f_{ab} = \frac{0.75*(0.049/6.00)}{0.75*(0.049/6.00) + 0.50*(0.084/20)}$$


$$D.f_{ab} = 0.74 \quad D.f_{ac} = 1 - 0.74 = 0.26$$

$$F.E.M. = 75.95 * 20^2 / 12 = 2532 \text{ kN}$$




1873.44


1873.44



312.24



759.5




Design of Sections

Sec. (1-1) $M_{u.l.} = 1873.44 \text{ kN.m}$

$N_{u.l.} = 759.50 \text{ kN.m}$

$b = 300 \text{ mm}$, $t = 1500 \text{ mm}$



$$\frac{N_{u.l.}}{b t f_{cu}} = \frac{759.50 \cdot 10^3}{300 \cdot 1500 \cdot 25} = 0.068 > 0.04 \quad (\text{Don't neglect } N_{u.l.})$$

$$e = \frac{M_{u.l.}}{N_{u.l.}} = \frac{1873.44}{759.50} = 2.47 \text{ m}$$

$$\frac{e}{t} = \frac{2.47}{1.50} = 1.64 > 0.5 \quad (\text{big eccentricity})$$

$$e_s = e + \frac{t}{2} - c = 2.47 + \frac{1.50}{2} - 0.1 = 3.12 \text{ m}$$

$$M_{us} = 759.50 \cdot 3.12 = 2367.12 \text{ kN.m}$$

$$d = C_1 \sqrt{\frac{M_{us}}{b \cdot f_{cu}}}$$

$$1400 = C_1 \sqrt{\frac{2367.12 \cdot 10^6}{300 \cdot 25}} \quad C_1 = 2.49 < 2.78 \quad \text{take } d = 1600 \text{ mm}$$

$$e_s = e + \frac{t}{2} - c = 2.47 + \frac{1.70}{2} - 0.1 = 3.22 \text{ m}$$

$$M_{us} = 759.50 \cdot 3.22 = 2445.59 \text{ kN.m}$$

$$1600 = C_1 \sqrt{\frac{2445.59 \cdot 10^6}{300 \cdot 25}} \quad C_1 = 2.80 \quad \& \quad J = 0.72$$

$$A_s = \frac{M_{us}}{J \cdot d \cdot f_y} - \frac{N_{us}}{f_y / \gamma_s}$$

$$A_s = \frac{2445.59 \cdot 10^6}{0.72 \cdot 1600 \cdot 360} - \frac{759.50 \cdot 10^3}{360 / 1.15}$$

$$A_s = 34.75 \text{ cm}^2 = 10 \emptyset 22$$

Sec. (2-2) $M_{u.l.} = 1873.44 \text{ kN.m}$ $N_{u.l.} = 312.24 \text{ kN.m}$

$b = 300 \text{ mm}$, $t = 1700 \text{ mm}$


$$\frac{N_{u.l.}}{b t f_{cu}} = \frac{312.24 * 10^3}{300 * 1700 * 25} = 0.024 < 0.04 \quad (\text{neglect } N_{u.l.})$$

$$d = C_1 \sqrt{\frac{M_{u.l.}}{b * f_{cu}}}$$

$$1600 = C_1 \sqrt{\frac{1873.44 * 10^6}{300 * 25}} \quad C_1 = 3.20 \quad \& \quad J = 0.76$$

$$A_s = \frac{1873.44 * 10^6}{0.76 * 1600 * 360}$$

$$A_s = 42.75 \text{ cm}^2 = 12 \emptyset 22$$



Sec. (3-3) $M_{u.l.} = 1924.06 \text{ kN.m}$ $N_{u.l.} = 312.24 \text{ kN.m}$

$b = 300 \text{ mm}$, $t = 1700 \text{ mm}$


$$\frac{N_{u.l.}}{b t f_{cu}} = \frac{312.24 * 10^3}{300 * 1700 * 25} = 0.024 < 0.04 \quad (\text{neglect } N_{u.l.})$$

$$d = C_1 \sqrt{\frac{M_{u.l.}}{b * f_{cu}}}$$

$$1600 = C_1 \sqrt{\frac{1924.06 * 10^6}{300 * 25}} \quad C_1 = 3.16 \quad \& \quad J = 0.76$$

$$A_s = \frac{1924.06 * 10^6}{0.76 * 1600 * 360}$$

$$A_s = 44.11 \text{ cm}^2 = 12 \emptyset 22$$



Check Shear

$$Q_{cr} = Q_{max} - w \left(\frac{c}{2} + \frac{d}{2} \right)$$

$$Q_{cr} = 759.5 - 75.95 \left(\frac{1.70}{2} + \frac{1.60}{2} \right)$$

$$Q_{cr} = 634.18 \text{ kN}$$

$$q_{su} = \frac{Q_{cr}}{bd} = \frac{634.18 \times 10^3}{300 \times 1600} = 1.32 \text{ N/mm}^2$$

$$q_{cu} = 0.24 \sqrt{\frac{25}{1.5}} = 0.98 \text{ N/mm}^2$$

$$q_{cu} < q_u < q_{u_{max}}$$

$$q_{max} = 0.7 \sqrt{\frac{25}{1.5}} = 2.86 \text{ N/mm}^2$$

$$q_u - \frac{q_{cu}}{2} = \frac{n A_s f_y}{b S}$$


assume $n=2$

$$A_s = 78.5 \text{ mm}^2 = \phi 10$$

$$1.32 - \frac{0.98}{2} = \frac{2 \times 78.5 \times 240 / 1.15}{300 \times S} \longrightarrow S = 131.59 \text{ mm}$$

$$\text{No. of stirrups/m} = \frac{1000}{S} = 7.6 \quad \text{Take Stirrups } 8\phi 10/\text{m}$$

R.F.T. of the Frame



Example


For the given plan, it is required to:

- 1-Choose the suitable system to cover this Area.
- 2-Design all Slabs and draw plan of Rft.
- 3-Design the main supporting element and draw details of Rft.

$$F.C.=1.5\text{kN/m}^2, L.L.=0.5 \text{ kN/m}^2$$

$$f_{cu}=25 \text{ N/mm}^2, f_y=360 \text{ N/mm}^2$$

Columns are only allowed on perimeter



Solution

$$t_s = \frac{560}{24} = 23.33\text{cm}$$


$$t_{s_{min}} = \frac{560}{35} = 16.00\text{cm}$$

take $t_s = 16 \text{ cm}$ (Check def.)



$$w_{su} = 1.4[t_s \gamma_c + F.c.] + 1.6 L.L. \cos \theta$$


$$w_{su} = 1.4[0.16 * 25 + 1.5] + 1.6 * 0.5 * 0.89$$

$$w_{su} = 8.41\text{kN/m}^2$$






$$\theta = \tan^{-1}\left(\frac{2.5}{5.0}\right) = 26.57^\circ$$






لاحظ في هذه الحالة يكون (Y-beam) هي ال (Sec.-beam)

حاول تخيل شكل البلاطات



1:200 → 1:400



Sec. (1-1)

$$140 = C_1 \sqrt{\frac{28.90 \cdot 10^6}{1000 \cdot 25}} \quad C_1 = 4.12 \quad J = 0.807$$

$$A_s = \frac{28.90 \cdot 10^6}{0.807 \cdot 360 \cdot 140} = 710 \text{ mm}^2 / \text{m}'$$

$$A_s = 7 \Phi 12 / \text{m}'$$

Sec. (2-2)

$$A_s = 5 \Phi 8 / \text{m}'$$

2] Reactions of slabs on beams

$$\Sigma M_a = 0$$


$$8.41 \cdot 5.60 \cdot 5.0 / 2 + 8.50 \cdot 0.5 \cdot 5.25 = R \cdot 5.00$$

$$R = 28.01 \text{ kN/m}$$

$$\Sigma y = 0$$

$$8.41 \cdot 5.60 + 8.50 \cdot 0.5 = R + y$$

$$y = 23.34 \text{ kN/m}$$




3] Analysis of Ridge beam (250*400)

$$w = R + o.w \quad \text{kN/m}$$

$$w = 28.01 + 0.25 \cdot 0.40 \cdot 25 \cdot 1.40$$

$$w = 31.51 \text{ kN/m}$$

$$R_1 = 31.51 \cdot 3.0 = 94.53 \text{ kN}$$




4] Design of Posts

$$R_p = R_1 + o.w \text{ of Post}$$

$$R_p = 94.53 + 0.25 * 0.25 * 2.5 * 25 * 1.40 = 100.00 \text{ kN}$$

$$100.00 * 10^3 = 0.35 * 250 * 250 * 25 + 0.67 A_s f_y$$

$$A_s = -ve \rightarrow A_s = 4\phi 13$$






5] Design of of Y-beam

$$w_y = 0.w + y + \frac{\Sigma R_p}{\text{Span}} \quad \text{kN/m}$$

$$w_y = 0.25 * 0.60 * 25 * 1.40 + 23.34 + \frac{2 * 100.0}{6.0}$$

$$w_y = 61.92 \text{ kN/m}$$

$$R_y = 61.92 * 6.0 = 371.54 \text{ kN}$$




6] Analysis of End beam

$$w_{vl} = 0.w + y \quad \text{kN/m}$$

$$w_{vl} = 0.25 * 0.60 * 25 * 1.40 + 23.34$$

$$w_{vl} = 28.59 \text{ kN/m}$$


$$R_{vl} = 28.59 * 6.0 = 171.54 \text{ kN}$$



7]Design of Main system

$$o.w. = 0.30 * 1.70 * 25 * 1.40$$

$$o.w. = 17.85 \text{ kN/m}$$



$$I_b = 0.3 * \frac{1.7^3}{12} = 0.123 \text{ m}^4$$

$$I_c = \frac{0.30 * \left(\frac{5}{6} * 1.70 \right)^3}{12}$$




$$I_c = 0.071 \text{ m}^4$$

For Joint a

$$D.f_{ab} = \frac{0.75(I_c/h)}{(0.75 \frac{I_c}{h}) + (0.5 \frac{I_b}{L})}$$


$$D.f_{ab} = \frac{0.75 * (0.071/6.00)}{0.75 * (0.071/6.00) + 0.50 * (0.123/20)}$$


$$D.f_{ab} = 0.72$$



2158.67

2158.67






Design of Sections

Sec. (1-1) $M_{u.l.} = 2158.67 \text{ kN.m}$ $N_{u.l.} = 907.35 \text{ kN}$

$b = 300 \text{ mm}$, $t = 1700 \text{ mm}$



$$\frac{N_{u.l.}}{b t f_{cu}} = \frac{907.35 \times 10^3}{300 \times 1700 \times 25} = 0.071 > 0.04 \quad (\text{Don't neglect } N_{u.l.})$$

$$e = \frac{M_{u.l.}}{N_{u.l.}} = \frac{2158.67}{907.35} = 2.37 \text{ m}$$

$$\frac{e}{t} = \frac{2.37}{1.70} = 1.39 > 0.5 \quad (\text{big eccentricity})$$

$$e_s = e + \frac{t}{2} - c = 2.37 + \frac{1.70}{2} - 0.1 = 3.12 \text{ m}$$

$$M_{us} = 907.35 \times 3.12 = 2832.07 \text{ kN.m}$$

$$d = C_1 \sqrt{\frac{M_{us}}{b * f_{cu}}}$$

$$1600 = C_1 \sqrt{\frac{2832.07 \times 10^6}{300 \times 25}} \quad C_1 = 2.60 < 2.78 \quad \text{take } d = 1800 \text{ mm}$$

$$e_s = e + \frac{t}{2} - c = 2.47 + \frac{1.90}{2} - 0.1 = 3.32m$$

$$M_{us} = 907.35 * 3.32 = 3012.40 kN.m$$

$$1800 = C_1 \sqrt{\frac{3012.40 * 10^6}{300 * 25}} \quad C_1 = 2.84 \quad \& \quad J = 0.72$$

$$A_s = \frac{M_{us}}{J.d.f_y} - \frac{N_{us}}{f_y / \gamma_s}$$

$$A_s = \frac{3012.40 * 10^6}{0.72 * 1800 * 360} - \frac{907.35 * 10^3}{360 / 1.15}$$

$$A_s = 35.18 cm^2 = 10 \emptyset 22$$

Sec. (2-2) $M_{u.l.} = 2158.67 kN.m$ $N_{u.l.} = 359.78 kN.m$

$b = 300 mm$, $t = 1900 mm$


$$\frac{N_{u.l.}}{b t f_{cu}} = \frac{359.78 * 10^3}{300 * 1900 * 25} = 0.025 < 0.04 \quad (\text{neglect } N_{u.l.})$$

$$d = C_1 \sqrt{\frac{M_{u.l.}}{b * f_{cu}}}$$

$$1800 = C_1 \sqrt{\frac{2158.67 * 10^6}{300 * 25}} \quad C_1 = 3.36 \quad \& \quad J = 0.77$$

$$A_s = \frac{2158.67 * 10^6}{0.77 * 1800 * 360}$$

$$A_s = 43.16 cm^2 = 12 \emptyset 22$$



Sec. (3-3) $M_{u.l.} = 2449.23 kN.m$ $N_{u.l.} = 359.78 kN.m$


$b = 300 mm$, $t = 1900 mm$

$$d = C_1 \sqrt{\frac{M_{u.l.}}{b * f_{cu}}}$$

$$1800 = C_1 \sqrt{\frac{2449.23 * 10^6}{300 * 25}} \quad C_1 = 3.15 \quad \& \quad J = 0.76$$

$$A_s = \frac{2449.23 * 10^6}{0.76 * 1800 * 360}$$

$$A_s = 49.96 \text{ cm}^2 = 11 \phi 25$$



Check Shear

$$Q_{cr} = Q_{max} - w \left(\frac{c}{2} + \frac{d}{2} \right)$$

$$Q_{cr} = 735.81 - 17.85 \left(\frac{1.90}{2} + \frac{1.80}{2} \right)$$

$$Q_{cr} = 702.79 \text{ kN}$$

$$q_{su} = \frac{Q_{cr}}{bd} = \frac{702.79 * 10^3}{300 * 1800} = 1.31 \text{ N/mm}^2$$

$$q_{cu} = 0.24 \sqrt{\frac{25}{1.5}} = 0.98 \text{ N/mm}^2$$

$$q_{cu} < q_u < q_{u_{max}}$$

$$q_{max} = 0.7 \sqrt{\frac{25}{1.5}} = 2.86 \text{ N/mm}^2$$


$$q_u - \frac{q_{cu}}{2} = \frac{n A_s f_y}{b S}$$

$$\text{assume } n=2 \quad A_s = 78.5 \text{ mm}^2 = \phi 10$$

$$1.31 - \frac{0.98}{2} = \frac{2 * 78.5 * 240 / 1.15}{300 * S} \quad \Rightarrow \quad S = 133.19 \text{ mm}$$

$$\text{No. of stirrups/m} = \frac{1000}{S} = 7.5 \quad \text{Take Stirrups } 8 \phi 10 / \text{m}$$

R.F.T. of the Frame



By Eng. Ezz El-Din Mostafa & Eng. Yasser M. Samir

Example

For the given plan, it is required to:

1-Choose the suitable system to cover this Area.


2-Design all Slabs and draw plan of Rft.

3-Design the main supporting element and draw details of Rft.

$$F.C.=1.5\text{kN/m}^2, L.L=0.5\text{ kN/m}^2$$

$$f_{cu}=32.5\text{ N/mm}^2, f_y=360\text{ N/mm}^2$$

Columns are only allowed on axes A,B,C




Solution

Use continuous frame

$$t = \frac{671}{16} = 41.94\text{cm}$$

$$\text{take } t=25\text{ cm } [20\text{cm}+5\text{cm}]$$





$$\theta = \tan^{-1}\left(\frac{3}{6.0}\right) = 26.57$$


$$w_{su} = 1.4(t_s \gamma_c + F.C. + 2bh \gamma_c + 10 * \text{wt. of block}) + 1.6 L.L. \cos \theta$$

$$w_{su} = 1.4(0.05 * 25 + 1.5 + 2 * 0.1 * 0.2 * 25 + 10 * 0.15) + 1.6 * 0.5 * 0.89$$

$$w_{su} = 8.06\text{kN/m}^2$$


$$w_{su/\text{Rib}} = 0.5 * 8.06 = 4.03\text{kN/m}$$







KEY PLAN

1:200 → 1:400



Side view



Sec. (1-1)

$$220 = C_1 \sqrt{\frac{20.28 \cdot 10^6}{500 \cdot 25}} \quad C_1 = 5.46 \quad J = 0.826$$

$$A_s = \frac{20.28 \cdot 10^6}{0.826 \cdot 360 \cdot 220} = 3.10 \text{ cm}^2 / \text{rib}$$

$$A_s = 2 \Phi 16 / \text{rib}$$


Sec. (2-2)

$$A_s = 2 \Phi 10 / \text{rib}$$

2] Reactions of slabs on beams

$$R = y = w_{su} \cdot \frac{L}{2} \quad \text{kN/m}$$

$$R = y = 8.06 \cdot 6.71 / 2 = 27.04 \text{ kN/m}$$




3] Analysis of Ridge beam (250*400)

$$w = R + o.w \quad \text{kN/m}$$

$$w = 27.04 + 0.25 \cdot 0.40 \cdot 25 \cdot 1.40$$

$$w = 30.54 \text{ kN/m}$$



$$R_1 = 30.54 \cdot 2.5 = 76.35 \text{ kN}$$

4] Design of Posts

$$R_p = R_1 + o.w \text{ of Post}$$

5]Design of main system





لاحظ في هذه الحالة يكون (Frame) هو نفسه (Y-beam)

لان الشكل متماثل يمكن اعتبار العمود الاوسط Link member


$$w_f = 0.w. + y + \frac{\Sigma R_p}{Span} \quad kN/m$$

$$w_f = 0.30 * 1.30 * 25 * 1.40 + 27.04 + \frac{12 * 82.91}{20.0}$$

$$w_f = 73.85 kN/m$$



$$I_b = 0.3 * \frac{1.3^3}{12} = 0.055 m^4$$



$$I_c = \frac{0.30 * \left(\frac{5}{6} * 1.30 \right)^3}{12}$$

$$I_c = 0.032 m^4$$

For Joint a


$$D.f_{ab} = \frac{0.75(I_c/h)}{(0.75 \frac{I_c}{h}) + (\frac{I_b}{L})}$$

$$D.f_{ab} = \frac{0.75*(0.032/6.00)}{0.75*(0.032/6.00) + (0.055/15)}$$

$$D.f_{ab} = 0.52 \quad D.f_{ac} = 1 - 0.52 = 0.48$$






$$F.E.M. = 73.85 * 15^2 / 12 = 1384.7 \text{ kN.m}$$

يحل نصف ال Frame لانه متماثل



Joint	c	a	
member	ca	ac	ab
D.F.	—	0.48	0.52
F.E.M.	1384.7	-1384.7	0.0
Bal. M	0.0	664.7	720
C.O.M.	332.3	0.0	0.0
Bal. M	0.0	0.0	0.0
M _{final}	1717	-720	720

73.85 kN/m



Sec. (1-1) $M_{u.l.} = 1717 \text{ kN.m}$

$N_{u.l.} = 120 \text{ kN}$

$b = 300 \text{ mm}$, $t = 1300 \text{ mm}$


$$\frac{N_{u.l.}}{b t f_{cu}} = \frac{120 * 10^3}{300 * 1300 * 25} = 0.009 < 0.04 \quad (\text{neglect } N_{u.l.})$$

$$d = C_1 \sqrt{\frac{M_{u.l.}}{b * f_{cu}}}$$

$$1200 = C_1 \sqrt{\frac{1717 * 10^6}{300 * 32.5}} \quad C_1 = 2.85 \quad \& \quad J = 0.74$$

$$A_s = \frac{1717 * 10^6}{0.74 * 1200 * 360}$$

$$A_s = 5371 \text{ mm}^2 = 11 \phi 25$$




Sec. (2-2) $M_{u.l.} = 858 \text{ kN.m}$

$N_{u.l.} = 120 \text{ kN}$
neglected

$$1200 = C_1 \sqrt{\frac{858 * 10^6}{300 * 32.5}} \quad C_1 = 4.0 \quad \& \quad J = 0.8$$

$$A_s = \frac{1924.06 * 10^6}{0.76 * 1600 * 360}$$

$$A_s = 2483 \text{ mm}^2 = 7 \phi 22$$



Sec. (3-3) $M_{u.l.} = 720 \text{ kN.m}$

$N_{u.l.} = 120 \text{ kN}$
neglected

$$A_s = 6 \phi 22$$

Sec. (4-4)

$$M_{u.l.} = 720 \text{ kN.m}$$

$$N_{u.l.} = 487.4 \text{ kN}$$

$$\frac{N_{u.l.}}{b t f_{cu}} = \frac{120 * 10^3}{300 * 1300 * 25} = 0.038 < 0.04 \quad (\text{neglect } N_{u.l.})$$

$$A_s = 6\phi 22$$

Check Shear

$$Q_{cr} = Q_{max} - w \left(\frac{c}{2} + \frac{d}{2} \right)$$

$$Q_{cr} = 620.3 - 73.85 \left(\frac{0.80}{2} + \frac{1.20}{2} \right)$$

$$Q_{cr} = 546.45 \text{ kN}$$

$$q_{su} = \frac{Q_{cr}}{b d} = \frac{546.45 * 10^3}{300 * 1200} = 1.52 \text{ N/mm}^2$$

$$q_{cu} = 0.24 \sqrt{\frac{32.5}{1.5}} = 1.12 \text{ N/mm}^2$$

$$q_{cu} < q_u < q_{u \max}$$

$$q_{\max} = 0.7 \sqrt{\frac{32.5}{1.5}} = 3.25 \text{ N/mm}^2$$

$$q_u - \frac{q_{cu}}{2} = \frac{n A_s f_y}{b S} \gamma_s$$

assume $n=2$

$$A_s = 78.5 \text{ mm}^2 = \phi 10$$

$$1.52 - \frac{1.12}{2} = \frac{2 * 78.5 * 240 / 1.15}{300 * S} \quad \longrightarrow \quad S = 113 \text{ mm}$$

$$\text{No. of stirrups/m} = \frac{1000}{S}$$

Take Stirrups $9\phi 10/\text{m}$

Design of Internal column

$$N_{u.l.} = 620.3 * 2 = 1240.6 \text{ kN}$$

$$\lambda_{b_{in}} = \frac{1.3 * 5.45}{0.8} = 8.8, \quad \lambda_{b_{out}} = \frac{1.2 * 6.25}{0.3} = 25 \quad \text{unsafe}$$

$$\text{Take } b_{col} = 35 \text{ cm}$$

$$\lambda_{b_{out}} = \frac{1.2 * 6.25}{0.35} = 21.4$$

Column is Long outside plan.

$$\delta_b = \frac{\lambda_{b_{out}}^2 * b}{2000} = \frac{21.4^2 * 0.35}{2000} = 0.08 \text{ m}$$

$$M_{add} = P * \delta_b = 1240.6 * 0.08 = 99 \text{ kN.m}$$


$$\frac{N_{u.l.}}{b t f_{cu}} = \frac{1240.6 * 10^3}{350 * 800 * 32.5} = 0.136, \quad \frac{M_{u.l.}}{b^2 t f_{cu}} = \frac{99 * 10^6}{350^2 * 800 * 32.5} = 0.03$$

$$\rho < 1 \quad \text{Take } \rho = 1$$


$$A_{smin} = \frac{0.25 + 0.052 * 21.4}{100} * 350 * 800 = 3816 \text{ mm}^2$$

16 Φ 18

R.F.T. of the Frame



R.F.T. of the Frame





Example

For the given plan, it is required to:

- 1-Choose the suitable system to cover this Area.
- 2-Design all Slabs and draw plan of Rft.
- 3-Design the main supporting element and draw details of Rft.


$$F.C.=1.5\text{ kN/m}^2, L.L=0.5\text{ kN/m}^2$$

$$f_{cu}=25\text{ N/mm}^2, f_y=360\text{ N/mm}^2$$




Columns are only allowed on perimeter

Two way slab لاحظ ان البلاطة تحل على انها



$$\theta = \tan^{-1}\left(\frac{1.85}{5.0}\right) = 20.3$$






$$r = \frac{0.76 \cdot 6.0}{5.33} = 0.85$$


$$r^* = 1.17$$

$$\alpha = 0.43$$


$$\beta = 0.25$$




Strip 1



Strip 2





Load distribution





Analysis of Ridge beam(250*400)

$$w=0.w. + \frac{\Sigma Area}{Span} w_{si}$$

$$R_1 = w * 2.5 = \text{-----} kN$$









Example

For the given plan and cross-section,

Columns are allowed on the perimeter only
it is required to:





- 1- Draw structural plan and cross section to show all concrete elements.
- 2- Show How to solve main systems






Solution

لاحظ ان الارض ليست مستطيلة
















For Frame(2)




المفروض يتم حله في الفراغ (Space frame) ولكن نظرا لصعوبة الحل يتم وضعه على (Neoprene plate) وبالتالي يصبح



Solving using virtual work method



For heavy frame




نتيجة لان (heavy frame) عليه أحمال ثقيلة فان

$$b=40\text{cm}, \quad t=\frac{L}{10} = \frac{20}{10} = 2.00\text{m}$$

$$w_a = w_e = \gamma_c b(t-t_s) * 1.40 + \frac{\Sigma \text{Area}}{\text{Span}} w_s + \frac{\Sigma \text{Concentrated loads}}{\text{Span}}$$

Where Concentrated loads are the loads from secondary
Beams & Frames



ثم نحله باستخدام (Moment Distribution)

